

Canal	Volumes per Canal				Total	
	-5.4 ft Dredge Template		-5.9 ft Overdredge Template		Sediment	Rock
MAIN B	1,102	152	698	52	1,800	204
MAIN B1	457	78	208	52	665	130
A-A	976	225	1,149	117	2,125	342
B-B	0	0	10	0	10	0
C-C	29	0	23	0	52	0
D-D	37	0	63	0	100	0
E-E	46	0	58	0	104	0
F-F	1	0	10	0	11	0
G-G	0	0	0	0	0	0
H-H	0	0	0	0	0	0
I-I	0	0	0	0	0	0
J-J	1	0	0	0	1	0
K-K	1	0	0	0	1	0
L-L	14	0	72	0	86	0
M-M	266	0	262	0	528	0
N-N	17	0	53	0	70	0
O-O	10	0	16	0	26	0
P-P	8	0	17	0	25	0
Q-Q	70	0	83	0	153	0
R-R	976	30	1,136	5	2,112	35
S-S	163	2	182	0	345	2
T-T	22	0	23	0	45	0
U-U	14	0	72	0	86	0
V-V	1,168	186	1,247	8	2,415	194
W-W	2,153	334	918	106	3,071	440
X-X	3,039	40	1,267	12	4,306	52
Y-Y	547	244	156	116	703	360
Z-Z	566	0	259	3	825	13
AA-AA	821	0	286	0	1,107	0
BB-BB	1,760	212	887	67	2,647	279
CC-CC	1,168	147	756	52	1,924	199
DD-DD	1,239	690	766	307	2,005	997



ATKINS 4030 Boy Scout Boulevard, Suite 700 Tampa, Florida 33607 Ph. (813) 282-7275 Fax (813) 636-8583 <small>FBRP CERTIFICATE OF AUTHORIZATION NO. 24</small>	CLIENT	CITY OF NAPLES	PROJECT	EAST NAPLES BAY DREDGING PROJECT	TASK	COMPLETED SEDIMENT DREDGING 1"=600'	ORIGINAL	JUNE 30, 2011	6. _____	<small>NOT VALID FOR CONSTRUCTION UNLESS SIGNED IN THIS BLOCK</small> JEFFREY R. TABAR, P.E. 54094	JOB NO.	093206.01
	1. DEC 06, 2011 2. JAN 27, 2012 3. MAR 03, 2012 4. MAR 15, 2012	7. _____	8. _____	9. _____	10. _____	11. _____	12. _____	DRAWN: MSS PE: JRT CHECKED: BDF QC: MSS	SHEET 01			