



1. Frame in new door opening. Install door with window from Phase 2 item # 11. Finish drywall and ceiling to match existing



2. Make existing door opening larger to accommodate new door. (Supplied by City). See dimensions in bid documents. Rework electrical as needed.



3. Remove door/jam and cabinets. Existing opening to be closed in with framing and drywall. Demoed double door to be transferred to adjacent side. Finish drywall and ceiling to match existing. (Rework electrical as needed)





4. Remove existing door and frame. Finish drywall and ceiling to match existing .



5. Remove 3 doors and 4 frames. Finish openings to match existing. Demo all interior walls, creating one room. (Labeled Storage Room) Finish drywall and ceiling to match existing.



6. Remove existing door and frame. Finish drywall and ceiling to match existing hallway.

7. Move door to align with adjacent door. (7A) is new door opening.







7. Frame in walls and door opening to create new closet. Use demoed closet door from phase 1 item 5. Add light fixture and switch for closet. Finish drywall and ceiling to match existing.





8. Remove existing wall creating one large room. Door remains where new wall ties in.  
Rework electrical and ceiling as needed (See phase 2 item # 9)

---



9. Frame/ drywall and finish new wall where existing opening is, and glass wall was removed. Rework ceiling to match existing.



10. Frame/drywall and finish around drainpipe. Finish drywall and ceiling to match existing.





11. Remove glass wall. (Rework drop ceiling as needed)



11. Remove door and frame. Reinstall with new glass window. (see phase 1 item 1)



Work  
Area

Dumpster  
Contractor  
Parking

Riverside Circle