

**20-009 - CSFD - NPD Flooring FWQ  
Attachment B - Floor Plan**

Unit	QTY	<b>NAPLES POLICE DEPARTMENT FLOORING PROJECT</b>	355
		RIVERSIDE CIRCLE NAPLES, FL 34102	
SF	626	Remove existing vinyl tile and install new LVT 16x16 Durango Gold TP509 (See color layout sheet)	
SF	2207	Remove existing carpet and install new Patcraft 24x24 carpet tile 10519 Scaffold (See color layout sheet)	
SF	960	Remove existing LVT and install new Patcraft 24x24 carpet tile 10519 Scaffold (See color layout sheet)	
SF	286	Remove existing carpet and install new LVT 16x16 Durango Gold TP509 (See color layout sheet)	
LS	1	Remove existing cove base and install new 4" x 1/8" cove base (Color TBT)	
LS	1	Provide and install all transitions as needed	
LS	1	Provide dumpster/ site cleanup/ protect belongings from dust/ Move furniture as needed	
SF	1000	Prep/float floor as needed per manufacturer specs	
SF	2207	Cover new carpet tiles in offices with Ram Board after installation	

