



CITY OF NAPLES

# Beach Outfall Project Community Meeting



## Topic of Discussion



### BEACH OUTFALL PROJECT

- Update on 3rd Avenue North Pump Station Design
- What to expect on directional drill project and schedule

**TUESDAY  
SEPTEMBER 13  
3:00PM**

COUNCIL CHAMBERS  
735 8TH ST S  
NAPLES, FL 34102

Questions regarding the  
meeting agenda or other  
matters may be  
directed to the  
City Clerk.


**Presentation begins at 3:00pm  
followed by Q & A session with staff**

FOR MORE INFORMATION, CONTACT:  
P: 239-213-1001  
E: MBARNHART@NAPLESGOV.COM



TO JOIN VIA ZOOM  
SCAN OR CLICK  
QR CODE

# South Pump Station - 90% Plan View (May 2022)



**116.7 ft or 5,201 sq. ft**

S:\2022\177310606\177310606.dwg (177310606) - 177310606.dwg (177310606) - 177310606.dwg (177310606) - 177310606.dwg (177310606) - 177310606.dwg (177310606)

Revision	City of Naples Comments	Rev	Appr	TY	MM	DD

Issued	SAH	RC	21.06.17
ISSUED 20% DESIGN DRAWINGS TO CITY (PRELIM REVIEW)	SAH	RC	21.06.17
ISSUED FINAL DESIGN	SAH	RC	20.09.14
ISSUED 80% DESIGN DRAWINGS	KME	APPROVED	18.03.14

Consultants

380 Polkman Bay Boulevard, Suite 300  
Naples, FL 34108  
www.stantec.com

2201 Delaney Court  
Sarasota, FL 34230  
www.ericksonconsultingengineers.com

Copyright Reserved

Client/Project

**CITY OF NAPLES**  
735 8th St S  
NAPLES, FL  
Naples Beach Restoration  
& Water Quality  
Improvement Project

File Name: 10606\_C1103.dwg

MP	SAH	RC	2022.04
Drawn	CME	Design	YYYYMM



Title

**PUMP STATION  
PROPOSED PAVEMENT AND  
DRAINAGE PLAN**

Project No. 177310606 Scale AS NOTED

Revision Drawing No. C-103

# SPS Plan Revision - Plan View (August 2022)



**88.1 ft or 3,887 sq. ft**

DURING CONSTRUCTION, CONTRACTOR SHALL REMOVE BEACH SIGN, PAVERS, BIKE RACK, FENCE AND OTHER ELEMENTS IN THIS AREA AND STORE AND SAFEGUARD UNTIL READY TO REINSTALL AFTER CONSTRUCTION. CONTRACTOR SHALL THEN RECONSTRUCT THIS AREA AS DIRECTED BY ENGINEER USING THESE ELEMENTS AND UP TO 400 SF OF 6" THICK CONCRETE SIDEWALK INCLUDING HANDICAP RAMP

LEGEND:

✕	SURVEY POINTS
✕	LIDAR POINTS
DESC ELEV	PROPOSED GRADE
→	FLOW ARROW

Revision	By	Appd.	Date	Comments
1	KME	APPROVED	18.07.12	CITY OF NAPLES COMMENTS

Issued	By	Appd.	Date	Comments
ISSUED 75% DESIGN DRAWINGS TO CITY (PRELIM REVIEW)	SAH	RC	21.05.17	
ISSUED FINAL DESIGN	SAH	RC	20.02.14	
ISSUED 60% DESIGN DRAWINGS	KME	APPROVED	18.03.14	

Consultants

5801 Pelican Bay Boulevard, Suite 300  
Naples, FL 34108  
www.stantec.com

7201 Delaney Court  
Sarasota, FL 32420  
www.ericksonconsultingengineers.com

Copyright Reserved  
The Contractor shall verify and be responsible for all dimensions. DO NOT scale the drawing - any errors or omissions shall be reported to Erickson Consulting Engineers (ECE) without delay. The Copyrights to all designs and drawings are the property of ECE. Reproduction or use for any purpose other than that authorized by ECE is forbidden.

Client/Project

CITY OF NAPLES  
735 8th St S  
NAPLES, FL  
Naples Beach Restoration & Water Quality Improvement Project

File Name: 10606.C-103.dwg

MPL	SAH	RC	2022.04
Dwn.	Chkd.	Desgn.	YYYY.MM

Title

PUMP STATION  
PROPOSED PAVEMENT AND  
DRAINAGE PLAN

Project No.  
177310606


Scale  
AS NOTED

Revision

Drawing No.  
C-103


X:\0226\erickson\shared\_projects\177310606\Drawings\01\_Scansystem\active\civil\sheet\10606\_C-103.dwg 2/22/2022 12:31:12 PM By: Lamerz, Mike

# SPS Plan Revision - Plan View (September 2022)



**Increased Ingress Width 7.1 ft. or 68%**

**66.7 ft or 2,492 sq. ft - Overall Reduction by 50 ft (43%) or 2,709 sq. ft total**



DURING CONSTRUCTION, CONTRACTOR SHALL REMOVE BEACH SIGN, PAVERS, BIKE RACK, FENCE AND OTHER ELEMENTS IN THIS AREA AND STORE AND SAFEGUARD UNTIL READY TO REINSTALL AFTER CONSTRUCTION. CONTRACTOR SHALL THEN RECONSTRUCT THIS AREA AS DIRECTED BY ENGINEER USING THESE ELEMENTS AND UP TO 400 SF OF 6" THICK CONCRETE SIDEWALK INCLUDING HANDICAP RAMP

**LEGEND:**

- x SURVEY POINTS
- o LIDAR POINTS
- DESC ELEV PROPOSED GRADE
- FLOW ARROW

Revision	By	Appd.	Date	Comments
1	KME	APPROVED	18.07.12	CITY OF NAPLES COMMENTS

Issued	By	Appd.	Date	Comments
ISSUED 75% DESIGN DRAWINGS TO CITY (PRELIM REVIEW)	SAH	RC	21.05.17	
ISSUED FINAL DESIGN	SAH	RC	20.02.14	
ISSUED 60% DESIGN DRAWINGS	KME	APPROVED	18.03.14	
Issued				

Consultants

5801 Pelican Bay Boulevard, Suite 300  
Naples, FL 34108  
www.stantec.com

**ECE**  
Erickson Consulting Engineers

7201 Delaney Court  
Sarasota, FL 32420  
www.ericksonconsultingengineers.com

Copyright Reserved

The Contractor shall verify and be responsible for all dimensions. DO NOT scale the drawing - any errors or omissions shall be reported to Erickson Consulting Engineers (ECE) without delay. The Copyrights to all designs and drawings are the property of ECE. Reproduction or use for any purpose other than that authorized by ECE is forbidden.

Client/Project

**CITY OF NAPLES**  
735 8th St S  
NAPLES, FL.  
Naples Beach Restoration & Water Quality Improvement Project

File Name: 10606.C-103.dwg

MPL	SAH	RC	2022.04
Dwn.	Chkd.	Dsgn.	YYYY.MM

Title


**PUMP STATION  
PROPOSED PAVEMENT AND  
DRAINAGE PLAN**

Project No. 177310606 Scale AS NOTED

Revision Drawing No. C-103


X:\0226\p1501\shared\_projects\177310606\Drawings\01\_Scans\System\active\civil\sheet\10606\_C-103.dwg 2022/09/20 3:25:24 PM by: latorra, latorra

# SPS Plan Revision – Section View (90% Plan May 2022)



**16.5 ft (Height above Ground)**

# SPS Plan Revision - Section View (August 2022)



- NOTES:**
- COORDINATE BOX CULVERT CONNECTION TO SCREEN CHAMBER AND PROVIDE ALL LABOR, MATERIALS, AND EQUIPMENT AS NECESSARY FOR COMPLETE ASSEMBLY.
  - REFER TO DRAWING S-605 FOR STRUCTURAL ELEVATIONS.

13.25 ft (Height above Ground)

\\nas010\proj\177310606\Drawings\177310606.dwg 2/2/2022 10:12:14 AM By: [redacted]

Revision	City of Naples Comments	By	Appd.	YYMMDD
1	CITY OF NAPLES COMMENTS	KME	APPROVED	18.07.12

Issued	By	Appd.	YYMMDD
ISSUED 75% DESIGN DRAWINGS TO CITY (PRELIM REVIEW)	SAH	RC	21.04.09
ISSUED FINAL DESIGN	SAH	RC	20.02.14
ISSUED 60% DESIGN DRAWINGS	KME	APPROVED	18.03.14

Consultants



5801 Pelican Bay Boulevard, Suite 300  
Naples, FL 34108  
www.stantec.com



7201 Delaney Court  
Sarasota, FL 32420  
www.ericksonconsultingengineers.com

Copyright Reserved  
The Contractor shall verify and be responsible for all dimensions. DO NOT scale the drawings. Any errors or omissions shall be reported to the Designer (ECC) without delay. The copyrights to all designs and drawings are the property of ECC. Reproduction or use for any purpose other than that authorized by ECC is forbidden.


Page 6 of 36

Client/Project

**CITY OF NAPLES**  
735 8th St S  
NAPLES, FL.  
Naples Beach Restoration  
& Water Quality  
Improvement Project

File Name: 10606\_C-301.dwg

MPL	SAH	RC	2022.04
Dwn.	Chk.	Dgn.	YYYY.MM




Title

**PUMP STATION  
PROPOSED GENERATOR SECTIONS**

Project No. 177310606 Scale AS NOTED

Revision Drawing No. C-301

# SPS Plan Revision - Section View (September 2022)



- NOTES:**
- COORDINATE BOX CULVERT CONNECTION TO SCREEN CHAMBER AND PROVIDE ALL LABOR, MATERIALS, AND EQUIPMENT AS NECESSARY FOR COMPLETE ASSEMBLY.
  - REFER TO DRAWING S-005 FOR STRUCTURAL ELEVATIONS.

**13.25 ft (Height above Ground) - Overall Reduction by 3.25 ft (20%) Total**  
**The diameter of the Axial draft tube is about 32 inches and extends 16-18 inches above top of concrete.**

X:\0226-0610-01\shared\_projects\177310606\Drawings\01\_Schematic\active\civil\sheet\10606\_C-301.dwg  
 2022/09/22 2:52 PM By: Lamerz, Mike

Revision	By	Appd.	YY.MM.DD	Comments
1	KME	APPROVED	18.07.12	CITY OF NAPLES COMMENTS

Issued	By	Appd.	YY.MM.DD	Comments
ISSUED 75% DESIGN DRAWINGS TO CITY (PRELIM REVIEW)	SAH	RC	21.04.09	
ISSUED FINAL DESIGN	SAH	RC	20.02.14	
ISSUED 60% DESIGN DRAWINGS	KME	APPROVED	18.03.14	

Consultants



5801 Pelican Bay Boulevard, Suite 300  
 Naples, FL 34108  
[www.stantec.com](http://www.stantec.com)



7201 Delaney Court  
 Sarasota, FL 32420  
[www.ericksonconsultingengineers.com](http://www.ericksonconsultingengineers.com)


**Copyright Reserved**  
 The Contractor shall verify and be responsible for all dimensions.  
 DO NOT scale the drawing - any errors or omissions shall be reported to Erickson Consulting Engineers (ECE) without delay.  
 The Copyrights to all designs and drawings are the property of ECE.  
 Reproduction or use for any purpose other than that authorized by ECE is forbidden.

Client/Project

**CITY OF NAPLES**  
 735 8th St S  
 NAPLES, FL.  
 Naples Beach Restoration  
 & Water Quality  
 Improvement Project

File Name: 10606\_C-301.dwg

MPL	SAH	RC	2022.04
Dwn.	Chkd.	Dsgn.	YYYY.MM




Title

**PUMP STATION  
 PROPOSED GENERATOR SECTIONS**

Project No. 177310606 Scale AS NOTED

Revision Drawing No. C-301

# Water Quality Improvement Goals (April 2022)





Pollutant	3- Lake System		South System	
	Baseline (mg/L)	% Removal	Baseline (mg/L)	% Removal
TSS (mg/l)	11.23	92%	47.10	79%
TN (mg/l)	1.70	62%	4.91	42%
TP (mg/l)	0.15	78%	0.79	46%

Flow to South Pump Station:  
68% 3-Lake System  
32% South System


Pollutant	Discharge	
TSS (mg/l)	3.86	mg/L
TN (mg/l)	1.35	mg/L
TP (mg/l)	0.16	mg/L



# BMP TREATMENT TRAIN




# BMP – Increase in Street Sweeping



Street Sweeping	Annual Reduction (lbs/yr) / (Percent)			20-Yr Costs per lb		
	TSS	TN	TP	TSS	TN	TP
3-Lake System	5336 64.5%	20 1.6%	13 10.6%	\$1	\$226	\$353
South System	2854 18%	14 1.00%	9 3.90%	\$1	\$168	\$262

# BMP – Hydrodynamic Separators





Flow to Downstream Defender

BMP	Annual Reduction (lbs/yr) / (Percent)			20-Yr Costs per lb		
	TSS	TN	TP	TSS	TN	TP
Hydrodynamic Separators	613 80%	78 22%	6 22%	\$20	\$154	\$1,988

BMP	Costs	
	Construction Costs	Annual Operation Cost
Hydrodynamic Separators	\$189,800	\$2,500


# BMP – Increase in Wet Detention



BMP	Annual Reduction (lbs/yr) / (Percent)			20-Yr Costs per lb		
	TSS	TN	TP	TSS	TN	TP
3-Lake System – Wet-Detention	250 12.5%	375.8 34%	51.6 59%	\$5	\$3	\$24

BMP	Costs	
	Construction Costs	Annual Operation Cost
3-Lake System – Wet Detention	\$5,000	\$500


# BMP – Aluminum Floatables Screen



BMP	Annual Reduction (lbs/yr) / (Percent)			20-Yr Costs per lb		
	TSS	TN	TP	TSS	TN	TP
Floatable Screen	500 6%	106.5 22%	7.9 22%	\$3	\$9	\$178

BMP	Costs	
	Construction Costs	Annual Operation Cost
Aluminum Floatables Screen	\$18,000	\$500


# BMP – Catch Basin Filter Basket Inserts



BMP	Annual Reduction (lbs/yr) / (Percent)			20-Yr Costs per lb		
	TSS	TN	TP	TSS	TN	TP
Catch Basin Filter Basket Inserts	4,511 74%	460 60%	85 71%	\$4	\$37	\$198

BMP	Costs	
	Construction Costs	Annual Operation Cost
Catch Basin Filter Basket Inserts	\$261,800	\$3,795

# BMP – Screening Chamber



BMP	Annual Reduction (lbs/yr) / (Percent)			20-Yr Costs per lb		
	TSS	TN	TP	TSS	TN	TP
Screening Chamber	6,115 60%	333 19.1%	31 15.5%	\$2	\$43	\$466

BMP	Costs	
	Construction Costs	Annual Operation Cost
Screening Chamber	\$188,300	\$5,000

# Alternatives

Alternative	Pump Station Location	Total Flow % Consolidated to Pump Station		System Re-Routing	Outfalls to Remain
		5-yr	25-yr		
1	3 <sup>rd</sup> Avenue N	77%	41%	To Moorings Bay & Naples Bay	Outfall 2 (Private Contribution)
2	6 <sup>th</sup> Avenue N (“North System”) <u>and</u> 3 <sup>rd</sup> Avenue N (“South System)	96%	69%	-	Outfall 2 (Private Contribution)
3	Vicinity of Naples Beach Hotel & Golf Club (“North System”) <u>and</u> 3 <sup>rd</sup> Avenue N (“South System)	100%	77%	-	-



# Alternatives: Conceptual Flow Schematics

## ALTERNATIVE #1 Single Pump Station @ 3<sup>rd</sup> Ave N



<b>5-yr</b>	<b>77%</b>
<b>25-yr</b>	<b>41%</b>

## ALTERNATIVE #2 Two Pump Stations @ 6<sup>th</sup> Ave N & 3<sup>rd</sup> Ave N



<b>5-yr</b>	<b>96%</b>
<b>25-yr</b>	<b>69%</b>

## ALTERNATIVE #3 Two Pump Stations @ Near Golf Club & 3<sup>rd</sup> Ave N



<b>5-yr</b>	<b>100%</b>
<b>25-yr</b>	<b>77%</b>

# Alternatives Evaluation & Ranking

- **Ranking by City Engr & Natural Resource Depts and Engr Team**
- **Meetings with Stakeholders**
  - **Conservancy of SWFL and Waterkeeper Alliance**
  - **Permitting Agencies (SFWMD, FDEP)**
- **Sensitivity Analysis**
- **Ranking Scale**

<b>Ranking</b>	<b>Description</b>
<b>-7 / +7</b>	<b>Significant comparative negative/positive project impact</b>
<b>-4 / +4</b>	<b>Medium comparative negative/positive project impact</b>
<b>0</b>	<b>Neutral impact for project</b>

# Alternatives Evaluation & Ranking

Evaluation Criteria	Weight	Alternative 1		Alternative 2		Alternative 3	
		Raw	Weighted	Raw	Weighted	Raw	Weighted
<b>Technical</b>	<b>40%</b>		<b>1.15</b>		<b>1.08</b>		<b>1.63</b>
Meets Project Objectives	15%	4	0.60	4	0.75	6	0.90
Technical Complexity (Pipeline Consolidation)	5%	-6	-0.30	-5	-0.25	-4	-0.20
Operational Integrity and Reliability (Pump Station)	7.5%	6	0.45	4	0.30	4	0.30
Constructability	7.5%	4	0.30	3	0.23	5	0.38
Scalability	5%	2	0.10	4	0.20	5	0.25
<b>Financial</b>	<b>30%</b>		<b>0.30</b>		<b>0.15</b>		<b>0.30</b>
Capital Expenditure (CAPEX)	15%	-1	-0.15	-3	-0.45	-3	-0.45
Effectiveness per Dollar Spent	15%	3	0.45	4	0.60	5	0.75
<b>Non-Technical</b>	<b>30%</b>		<b>1.30</b>		<b>1.23</b>		<b>1.68</b>
Social Considerations	7.5%	4	0.30	2	0.15	5	0.38
Environmental Impact	10%	4	0.40	5	0.50	6	0.60
Regulatory Approvals (Permitting)	5%	6	0.30	4	0.20	5	0.25
Health & Safety (Flood Protection, Public Safety, Recreation, etc)	7.5%	4	0.30	5	0.38	6	0.45
	<b>100%</b>		<b>2.8</b>		<b>2.5</b>		<b>3.6</b>


# Preferred Alternative

- **Alternative 3: Two pump stations**
- **Removes All City Outfalls (9)**
- **Routes Outfall 5 to Alligator Lake  
(Additional WQ Treatment)**
- **Significantly Improves Nearshore Water Quality**
- **Highest Effectiveness per Dollar Spent  
(100% / 77% of flows treated)**
- **Eliminates Adverse Impacts to  
Environmental Resources**
- **Scalable**

North Pump Station  
on Golf Course  
(exact location to be  
determined)

System Generator →


South System  
Pump Station  
& Electrical  
System →



# Gulf of Mexico Set Up

Plan Design & Solution

Pull Pipe from Water or Land – Both can be done



**Catch Rig: Universal 250x400 – will be placed on jack-up barge (#1)**



-Potential Pilot Hole Rig - A

**Barge and Drill Rig Gulf of Mexico Set-up**



**Catch Rig #1**

## Primary Drill #2




**American Auger DD440-T  
440,000 ft/lbs of drilling thrust**

# Land Side Set Up

Plan Design & Solution

Pull Pipe from Water or Land – Both can be done



# Pilot Hole Construction

During progress meetings, DBE has mentioned that we would like to mobilize either a Ditch Witch JT100 or the Universal 250x400 drill rig to perform the initial pilot hole construction. For visual reference on the above graphic, these are the 2 single small lines extending from the land into the water with a curved horizontal radius.





The JT 100 is a versatile drill that allows for a small footprint to be maintained. As you can see in the photo above, this rig is able to self-load rod baskets by using its onboard crane arm, without needing a separate excavator and stack of rods that double the width of our footprint. Using the available 100,000 ft/lbs of torque (or 250,000 ft/lbs with the Uni rig), this machine will be used to construct the pilot hole, which is approximately 8-9 inches in diameter. However, during this initial portion of hole construction, the ocean floor will not be breached by the tooling. This will prevent a release of bentonite drill mud into the Gulf which could create a turbid event. A breach will not occur until a casing is installed. Moreover, DBE will turn off the down-hole mud pump when there are between 1-3 drill rods remaining before exiting the surface. This will also ensure the heavier drill mud stays within the bore hole and keeps it from collapsing.

### **Enlarging the Bore Hole**


Once each pilot hole is constructed with the shown horizontal radius, the drill rods will be disconnected land-side and will be hooked up to a maxi rig with either 440,000 or 1.1 million ft/lbs of torque to ream and enlarge the pilot hole to approximately 42-inches in diameter. Depending on the deployment status of our maxi rigs, DBE will either mobilize the American Augers DD440-T or DD1100-RS. Each machine provides more than enough torque to ream the bore holes to prescribed diameter before readying the pipe(s) for pullback. DBE does not plan to breach the ocean floor with drill tooling until a steel conductor casing is driven from the barge into the ocean floor which will be used to contain drill mud and allow the tooling to be connected to the barge-based drill rig. The Universal 250x400 that may have been relocated from land-side to the barge after pilot hole construction (if this is the rig used), will help the land-based rig to rotate the drill string, but its main purpose will be to pull the pipes into final positioning from the ocean.

In addition to the drill rig based on land, DBE will also be placing a mud reclaimer (American Augers MCD-1000), otherwise known as a recycler within the beachside parking area during construction. This machine mixes bentonite with water to create drilling mud that is pumped through the drill stem to lubricate our downhole tooling and to build a wall cake that keeps the hole from collapsing as we push ream the hole. Through a closed loop system, the mud is flowed back from the drill head to the entry pit where it is pumped into the recycler and crosses over numerous varying sieve size screens with shakers to remove dirt, sand and other downhole particulates from the liquid mud that will be sent back to the drill head once cleaned. This prevents DBE from having to continually make more mud, which causes more waste for disposal when complete. For reference, please see the proposed site plan in page 7 below.

## Recycler Unit



## American Augers MCD-1000 Mud Reclaimer



## **Staging & Pulling Pipe**

**DBE intends to pull the new stormwater discharge pipes from the jack-up barge staged approximately 1,300 feet offshore of 3<sup>rd</sup> Ave. North. To accomplish this, FPVC pipe will be moved from the anticipated staging area at the WTP near the airport to the southeast corner of the Gulf Shore Blvd & 3<sup>rd</sup> Ave. North intersection. Pipe will be transported to the jobsite using a pipe trailer and offloaded in the grass a few sticks at a time. This will allow the fusion and stacking to begin. The operation is anticipated to begin just after we've initiated the pilot hole construction so that impact to the area is minimized.**

**Once unloaded at the construction site, DBE and Underground Solutions will close a small portion of the road to begin fusion operations, within a 200 LF portion of the southern travel lane (from west to east) along 3<sup>rd</sup> Avenue North. Pipe joints will be thermally butt fused and staged in 180 LF segments in the area identified below, within City ROW between the edge of pavement and the royal trees.**

**We will stack pipe in 180 LF segments a total of 3 levels high; 3 on bottom, 2 in the middle and 1 on top. Each pipe will be lashed to the others so they will not fall or slide out. These segments will be stacked on 4x4 or 6x6 lumber perpendicular to the travel lane and flow of the swale. There is a stormwater catch basin at the intersection that lies just above the existing grade of the swale. This is a likely culprit for street flooding, but by placing the lumber perpendicular, the water may continue to flow toward the catch basin, under our fused pipe segments if there is a rain event. Moreover, if the street begins to flood, DBE will have a vacuum unit onsite that can assist in sucking up overflow and discharging it directly into the storm system.**

**The day before each pipe pullback, DBE will close down 3<sup>rd</sup> Ave. North so that the 180 foot lengths may be fused into a single 800-900 LF segment. This segment will take up an entire travel lane of 3<sup>rd</sup> Ave. North from Gulf Shore Blvd to 3<sup>rd</sup> Street North. This leaves a single 180 LF segment left to be attached to complete the pipe string. However, DBE must close down Gulf Shore Blvd entirely to north/southbound traffic to pull the pipe across the street and into the bore entry pit. Once the segment is lying across Gulf Shore, the final piece can be fused on to complete the approximately 1,100 LF discharge line. The closings will have to occur twice to accommodate each new discharge line, a maximum of 2 days per occurrence.**

**The Universal 250x400 drill will extend its drill string from the exit pit on the ocean floor all the way to the entry pit on land and connect to the pipe string pull-head using a swivel. Once attached and pulled into position at the entry pit on land, DBE will begin filling the pipe with ballast water as it enters the mudline. This will reduce vertical forces on the pipe and ensure it stays at the bottom of the hole, instead of floating along the top causing more friction.**

**Once pulled into place, the segment will be capped for pressure testing. The drill rig(s) will be moved north or south, depending on which line is installed first for horizontal separation, and the process repeated to install the 2<sup>nd</sup> and final stormwater discharge line. Upon both lines**


being pulled into final position, an official pressure test will be conducted, the ends capped under water and landside, and buried on land until the subsequent pump station construction is ready to connect onto them for commissioning.

DBE will then restore the asphalt through mill & resurfacing, replace landscaping that was disturbed, and reopen the beach parking areas on 3<sup>rd</sup> Avenue North.






ID	Task Mode	Task Name	Duration	Start	Finish	% Complete	Predecessors	August		September			October				November			December														
								7/31	8/7	8/14	8/21	8/28	9/4	9/11	9/18	9/25	10/2	10/9	10/16	10/23	10/30	11/6	11/13	11/20	11/27	12/4	12/11	12/18	12/25					
1		<b>Contract Date</b>	0 days	Mon 2/28/22	Mon 2/28/22	0%																												
2		FPVC Materials Lead Time (project to begin prior to pipe delivery task 14)	151 days	Mon 2/28/22	Mon 9/26/22	0%	1																											
3		Pre-construction Video Survey	1 day	Tue 9/27/22	Tue 9/27/22	0%	2																											
4		Site Survey	2 days	Wed 9/28/22	Thu 9/29/22	0%	3																											
5		Confirm Permits & Utility Locates	1 day	Fri 9/30/22	Fri 9/30/22	0%	4																											
6		Mobilize: Drill Set-up	5 days	Mon 10/3/22	Fri 10/7/22	0%	5																											
7		Wire Line Grid	5 days	Mon 10/3/22	Fri 10/7/22	0%	6SS																											
8		Environmental Monitoring	5 days	Mon 10/3/22	Fri 10/7/22	0%	6SS																											
9		<b>HDD #1 - Pilot Shot</b>	3 days	Mon 10/10/22	Wed 10/12/22	0%	6,7,8																											
10		<b>HDD #2 - Pilot Shot</b>	3 days	Thu 10/13/22	Mon 10/17/22	0%	9																											
11		Float Jack-up Barge Into Place, Weld & Drive Casing	5 days	Thu 10/13/22	Wed 10/19/22	0%	9																											
12		<b>HDD #1</b>				0%																												
13		Ream #1	4 days	Thu 10/20/22	Tue 10/25/22	0%	10,11																											
14		Material Delivery	1 day	Thu 10/20/22	Thu 10/20/22	0%	13SS																											
15		Begin Pipe Fusion #1	3 days	Fri 10/21/22	Tue 10/25/22	0%	14																											
16		Pull-back #1	1 day	Wed 10/26/22	Wed 10/26/22	0%	13,15																											
17		Move Rig for 2nd Shot	2 days	Thu 10/27/22	Fri 10/28/22	0%	16																											
18		<b>HDD #2</b>				0%																												
19		Ream #2	4 days	Mon 10/31/22	Thu 11/3/22	0%	17																											
20		Begin Pipe Fusion #2	3 days	Mon 10/31/22	Wed 11/2/22	0%	19SS																											
21		Pull-back #2 daylight savings time 11/6	1 day	Fri 11/4/22	Fri 11/4/22	0%	19,20																											
22		De-Mob Drill	3 days	Mon 11/7/22	Wed 11/9/22	0%	21																											
23		Pressure Test New 30-inch Discharge Lines	2 days	Thu 11/10/22	Fri 11/11/22	0%	22																											
24		<b>Completion Tasks</b>				0%																												
25		Beach Parking Restoration, Backfilling & Compaction	3 days	Mon 11/14/22	Wed 11/16/22	0%	23																											
26		Asphalt Trench Restoration and Mill & Resurface	2 days	Thu 11/17/22	Fri 11/18/22	0%	25																											
27		Landscaping	3 days	Mon 11/21/22	Wed 11/23/22	0%	26																											
28		Punch List/Asbuilts	21 days	Thu 11/24/22	Thu 12/22/22	0%	27																											
29		Final Completion	1 day	Fri 12/23/22	Fri 12/23/22	0%	28																											



Project: City of Naples Schedule  
Date: Thu 7/21/22

Task		Project Summary		Manual Task
Split		Inactive Task		Duration-only
Milestone		Inactive Milestone		Manual Summary Rollup
Summary		Inactive Summary		Manual Summary

	Start-only		External Tasks		Deadline
	Finish-only		External Milestone		Progress
	Manual Progress				




Project: Equipment & Material  
Date: Tue 5/17/22

Task	Summary	Inactive Milestone	Duration-only	Start-only	External Milestone	Manual Progress
Split	Project Summary	Inactive Summary	Manual Summary Rollup	Finish-only	Deadline	Manual Progress
Milestone	Inactive Task	Manual Task	Manual Summary	External Tasks	Progress	Manual Progress



# TEMPORARY PEDESTRIAN WALKWAY



TEMPORARY TRAFFIC CONTROL SHALL COMPLY WITH THE CURRENT EDITION OF THE FDOT DESIGN STANDARDS (102-600 SERIES INDEX NUMBERS) AND MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (MUTCD).





# PIPE FUSION & STAGING



VARIABLE MESSAGE BOARDS LABELED (A) TO DISPLAY THE FOLLOWING MESSAGE 7 DAYS PRIOR TO WORK COMMENCEMENT:

PANEL 1	PANEL 2
ROAD TO BE CLOSED	MM/DD/YY THRU MM/DD/YY

VARIABLE MESSAGE BOARD LABELED (B) TO DISPLAY THE FOLLOWING MESSAGE 7 DAYS PRIOR TO WORK COMMENCEMENT:

PANEL 1	PANEL 2
BEACH ACCESS CLOSED	MM/DD/YY THRU MM/DD/YY

TEMPORARY TRAFFIC CONTROL SHALL COMPLY WITH THE CURRENT EDITION OF THE FDOT DESIGN STANDARDS (102-600 SERIES INDEX NUMBERS) AND MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (MUTCD).

PIPE STAGING ALONG EDGE OF PAVEMENT, WITHIN UTILITY EASEMENT 180'

**TEMPORARY SIGN SUPPORT NOTES:**

- All signs shall be post mounted when work operations exceed one day except for:
  - Road closure signs mounted in accordance with the vendor drawing for the Type III Barricade shown on the APL.
  - Pedestrian advanced warning or pedestrian regulatory signs mounted on sign supports in accordance with the vendor drawing shown on the APL.
  - Median barrier mounted signs per Index 700-013.

MOT provided by:  
**Bob's BARRICADES, INC.**  
 COMPLETE WORKSITE TRAFFIC CONTROL

**PLAN NOT TO SCALE**

**LEGEND**

= WORK AREA

= VARIABLE MESSAGE BOARD

**FDOT** This Certifies that **CAMERON BERGER**

Has Completed a Florida Department of Transportation Approved Temporary Traffic Control (TTC) Advanced (Refresher) Course.

Date Expires: 08/20/2025 Certificate # 76723  
 Instructor: Ronald C. Appel FDOT Provider # 134

A&S Consultants, Inc.  
 Phone: 386-788-9899  
 5545 Benchmark Lane  
 Sanford &nbsp;, FL 32773  
 www.FloridaMOT.com  
 nicolle@aswconsultants.com



PIPE PULLBACK  
APPROX 8 HOUR DURATION

PANEL 1 ROAD CLOSED AHEAD  
PANEL 2 FOLLOW DETOUR AHEAD

PANEL 1 S/B GULFSHOR CLOSED  
PANEL 2 FOLLOW DETOUR

PANEL 1 3RD AVE W/B CLOSED  
PANEL 2 FOLLOW DETOUR

PANEL 1 ROAD CLOSED AHEAD  
PANEL 2 FOLLOW DETOUR

PANEL 1 3RD AVE W/B CLOSED  
PANEL 2 FOLLOW DETOUR

PANEL 1 N/B GULFSHOR CLOSED  
PANEL 2 FOLLOW DETOUR

VARIABLE MESSAGE BOARDS LABELED (A) TO DISPLAY THE FOLLOWING MESSAGE 7 DAYS PRIOR TO WORK COMMENCEMENT:

PANEL 1 ROAD-SIDEWALK TO BE  
PANEL 2 CLOSED MM/DD/YY XXAM-XXPM

PANEL 1 ROAD CLOSED AHEAD  
PANEL 2 FOLLOW DETOUR

LEGEND  
[Hatched Box] = WORK AREA  
[Variable Message Board] = VARIABLE MESSAGE BOARD

TEMPORARY SIGN SUPPORT NOTES:  
1. All signs shall be post mounted when work operations exceed one day except for:  
a. Road closure signs mounted in accordance with the vendor drawing for the Type III Barricade shown on the APL.  
b. Pedestrian advanced warning or pedestrian regulatory signs mounted on sign supports in accordance with the vendor drawing shown on the APL.  
c. Median barrier mounted signs per Index 700-013.

MOT provided by: Bob's BARRICADES, INC. COMPLETE WORKSITE TRAFFIC CONTROL

PLAN NOT TO SCALE

FDOT This Certifies that CAMERON BERGER Has Completed a Florida Department of Transportation Approved Temporary Traffic Control (TTC) Advanced (Refresher) Course. Date Expires: 08/20/2025 Instructor: Ronald C. Appel Certificate # 76723 FDOT Provider # 134 A&S Consultants, Inc. Phone: 386-788-9899 5545 Benchmark Lane Sanford, FL 32773 www.FloridaMOT.com nicolle@aswconsultants.com

TEMPORARY TRAFFIC CONTROL SHALL COMPLY WITH THE CURRENT EDITION OF THE FDOT DESIGN STANDARDS (102-600 SERIES INDEX NUMBERS) AND MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (MUTCD).

**End of  
Presentation  
Q & A  
Thank you**