



CITY OF NAPLES

Beach Outfall Project Community Meeting



Topic of Discussion



BEACH OUTFALL PROJECT

- Update on 3rd Avenue North Pump Station Design
- What to expect on directional drill project and schedule

**TUESDAY
SEPTEMBER 13
3:00PM**

**COUNCIL CHAMBERS
735 8TH ST S
NAPLES, FL 34102**

Questions regarding the
accession of documents
offices may be
submitted to this
office.


**Presentation begins at 3:00pm
followed by Q & A session with staff**

FOR MORE INFORMATION, CONTACT:
P: 239-213-1001
E: MBARNHART@NAPLESGOV.COM



**TO JOIN VIA ZOOM
SCAN OR CLICK
QR CODE**

South Pump Station - 90% Plan View (May 2022)



116.7 ft or 5,201 sq. ft

DURING CONSTRUCTION, CONTRACTOR SHALL REMOVE BEACH SIGN, PAVERS, BIKE RACK, FENCE AND OTHER ELEMENTS IN THIS AREA AND STORE AND SAFEGUARD UNTIL READY TO REINSTALL AFTER CONSTRUCTION. CONTRACTOR SHALL THEN RECONSTRUCT THIS AREA AS DIRECTED BY ENGINEER USING THESE ELEMENTS AND UP TO 400 SF OF 6" THICK CONCRETE SIDEWALK INCLUDING HANDICAP RAMP

LEGEND:
 SURVEY POINTS
 LIDAR POINTS
 DESC (ELEV)
 PROPOSED GRADE

Revision	DATE	BY	APP'D	DESCRIPTION
1				CITY OF NAPLES COMMENTS

NO.	DATE	BY	APP'D	DESCRIPTION
1	05/02/22			ISSUED FOR PERMITS
2	05/02/22			ISSUED FOR PERMITS

Consultants

380 Polkton Bay Boulevard, Suite 300
 Naples, FL 34108
 www.stantec.com

ECE
 Erickson Consulting Engineers

7201 Oaklawn Court
 Sarasota, FL 34240
 www.ericksonconsulting.com

Copyright Reserved
 Page 10 of 35

Client/Project
CITY OF NAPLES
 735 8th St S
 NAPLES, FL
 Naples Beach Restoration
 & Water Quality
 Improvement Project


Title
**PUMP STATION
 PROPOSED PAVEMENT AND
 DRAINAGE PLAN**

Project No. 177310606 Scale AS NOTED
 Revision Drawing No. C-103

SPS Plan Revision - Plan View (September 2022)

Increased Ingress Width 7.1 ft. or 68%

66.7 ft or 2,492 sq. ft - Overall Reduction by 50 ft (43%) or 2,709 sq. ft total



DURING CONSTRUCTION, CONTRACTOR SHALL REMOVE BEACH SIGN, PAVERS, BIKE RACK, FENCE AND OTHER ELEMENTS IN THIS AREA AND STORE AND SAFEGUARD UNTIL READY TO REINSTALL AFTER CONSTRUCTION. CONTRACTOR SHALL THEN RECONSTRUCT THIS AREA AS DIRECTED BY ENGINEER USING THESE ELEMENTS AND UP TO 400 SF OF 6" THICK CONCRETE SIDEWALK INCLUDING HANDICAP RAMP

LEGEND:

- x SURVEY POINTS
- LIDAR POINTS
- DESC ELEV PROPOSED GRADE
- FLOW ARROW

Revision	By	Appd.	Y/M/D
1	CITY OF NAPLES COMMENTS	KOE	10/07/22

Issued	By	Appd.	Y/M/D

Consultants

5801 Pelican Bay Boulevard, Suite 300
Naples, FL 34109
www.stantec.com

ECE
Erickson Consulting Engineers


7201 Delaney Court
Sarasota, FL 32420
www.ericksonconsultingengineers.com

Copyright Reserved
The Contractor and user are responsible for all dimensions. DO NOT scale the drawing - any errors or omissions shall be reported to Erickson Consulting Engineers (ECE) without delay. The Copyrights to all designs and drawings are the property of ECE. Reproduction or use for any purpose other than that authorized by ECE is forbidden.

Client/Project
CITY OF NAPLES
735 8th St S
NAPLES, FL
Naples Beach Restoration & Water Quality Improvement Project

File Name: 1006_C-103.dwg

DRN	SAH	RC	2022/09
CHK	CHK	DRN	1/1/1/1




Title
PUMP STATION
PROPOSED PAVEMENT AND
DRAINAGE PLAN

Project No. 177310606
Scale AS NOTED

Revision _____ Drawing No. C-103

SPS Plan Revision - Section View (August 2022)



13.25 ft (Height above Ground)

I:\Projects\2022\SPS\Drawings\SPS_Plan_Revision_August_2022.dwg
 17/08/2022 11:27 AM
 User: jason.g...
 Plot: SPS_Plan_Revision_August_2022.dwg
 Plot Date: 17/08/2022 11:27 AM
 Plot Scale: 1:1
 Plot Device: HPGL
 Plot Path: I:\Projects\2022\SPS\Drawings\SPS_Plan_Revision_August_2022.dwg

Revision	City of Naples Comments	By	Appr	Yr/Mo/D
1	CITY OF NAPLES COMMENTS	GAE	APPROVED	18.07.12
		By	Appr	Yr/Mo/D

Issued	By	Appr	Yr/Mo/D
ISSUED FOR DESIGN DRAWINGS TO CITY (PRELIM REVIEW)	SAH	IC	21.04.09
ISSUED FINAL DESIGN	SAH	IC	30.05.14
ISSUED FOR DESIGN DRAWINGS	GAE	APPROVED	18.03.14
Issued	By	Appr	Yr/Mo/D

Consultants



3801 Pelican Bay Boulevard, Suite 300
Naples, FL 34109
www.stantec.com



7201 Delaney Court
Sarasota, FL 34240
www.ece-engineers.com

Copyright Reserved


The Contractor shall verify and be responsible for all dimensions.
The City of Naples shall not be responsible for any errors or omissions that may occur.
The City of Naples shall not be responsible for any errors or omissions that may occur.
The City of Naples shall not be responsible for any errors or omissions that may occur.

Client/Project

CITY OF NAPLES
735 8th St S
NAPLES, FL
Naples Beach Restoration & Water Quality Improvement Project

No. 177310606

APP	SAH	IC	2022.04
Dwn	Chic	Dgn	TTTJ.AM



Title

PUMP STATION
PROPOSED GENERATOR SECTIONS


Project No. 177310606

Scale AS NOTED


Revision

Drawing No. C-301


Water Quality Improvement Goals (April 2022)



BMP TREATMENT TRAIN




BMP – Increase in Street Sweeping



Street Sweeping	Annual Reduction (lbs/yr) / (Percent)			20-Yr Costs per lb		
	TSS	TN	TP	TSS	TN	TP
3-Lake System	5336 64.5%	20 1.6%	13 10.6%	\$1	\$226	\$353
South System	2854 18%	14 1.00%	9 3.90%	\$1	\$168	\$262

BMP – Hydrodynamic Separators




Flow to Downstream Defender

BMP	Annual Reduction (lbs/yr) / (Percent)			20-Yr Costs per lb		
	TSS	TN	TP	TSS	TN	TP
Hydrodynamic Separators	613 80%	78 22%	6 22%	\$20	\$154	\$1,988

BMP	Costs	
	Construction Costs	Annual Operation Cost
Hydrodynamic Separators	\$189,800	\$2,500



BMP – Increase in Wet Detention



BMP	Annual Reduction (lbs/yr) / (Percent)			20-Yr Costs per lb		
	TSS	TN	TP	TSS	TN	TP
3-Lake System – Wet-Detention	250 12.5%	375.8 34%	51.6 59%	\$5	\$3	\$24

BMP	Costs	
	Construction Costs	Annual Operation Cost
3-Lake System – Wet Detention	\$5,000	\$500


BMP – Aluminum Floatables Screen



BMP	Annual Reduction (lbs/yr) / (Percent)			20-Yr Costs per lb		
	TSS	TN	TP	TSS	TN	TP
Floatable Screen	500 6%	106.5 22%	7.9 22%	\$3	\$9	\$178

BMP	Costs	
	Construction Costs	Annual Operation Cost
Aluminum Floatables Screen	\$18,000	\$500


BMP – Catch Basin Filter Basket Inserts



BMP	Annual Reduction (lbs/yr) / (Percent)			20-Yr Costs per lb		
	TSS	TN	TP	TSS	TN	TP
Catch Basin Filter Basket Inserts	4,511 74%	460 60%	85 71%	\$4	\$37	\$198

BMP	Costs	
	Construction Costs	Annual Operation Cost
Catch Basin Filter Basket Inserts	\$261,800	\$3,795

BMP – Screening Chamber



BMP	Annual Reduction (lbs/yr) / (Percent)			20-Yr Costs per lb		
	TSS	TN	TP	TSS	TN	TP
Screening Chamber	6,115 60%	333 19.1%	31 15.5%	\$2	\$43	\$466

BMP	Costs	
	Construction Costs	Annual Operation Cost
Screening Chamber	\$188,300	\$5,000

Alternatives

Alternative	Pump Station Location	Total Flow % Consolidated to Pump Station		System Re-Routing	Outfalls to Remain
		5-yr	25-yr		
1	3 rd Avenue N	77%	41%	To Moorings Bay & Naples Bay	Outfall 2 (Private Contribution)
2	6 th Avenue N (“North System”) <u>and</u> 3 rd Avenue N (“South System”)	96%	69%	-	Outfall 2 (Private Contribution)
3	Vicinity of Naples Beach Hotel & Golf Club (“North System”) <u>and</u> 3 rd Avenue N (“South System”)	100%	77%	-	-

Alternatives: Conceptual Flow Schematics



5-yr	77%
25-yr	41%



5-yr	96%
25-yr	69%



5-yr	100%
25-yr	77%

Alternatives Evaluation & Ranking

- **Ranking by City Engr & Natural Resource Depts and Engr Team**
- **Meetings with Stakeholders**
 - **Conservancy of SWFL and Waterkeeper Alliance**
 - **Permitting Agencies (SFWMD, FDEP)**
- **Sensitivity Analysis**

➤ **Ranking Scale**

Ranking	Description
-7 / +7	Significant comparative negative/positive project impact
-4 / +4	Medium comparative negative/positive project impact
0	Neutral impact for project

Alternatives Evaluation & Ranking

Evaluation Criteria	Weight	Alternative 1		Alternative 2		Alternative 3	
		Raw	Weighted	Raw	Weighted	Raw	Weighted
Technical	40%		1.15		1.08		1.63
Meets Project Objectives	15%	4	0.60	4	0.75	6	0.90
Technical Complexity (Pipeline Consolidation)	5%	-6	-0.30	-5	-0.25	-4	-0.20
Operational Integrity and Reliability (Pump Station)	7.5%	6	0.45	4	0.30	4	0.30
Constructability	7.5%	4	0.30	3	0.23	5	0.38
Scalability	5%	2	0.10	4	0.20	5	0.25
Financial	30%		0.30		0.15		0.30
Capital Expenditure (CAPEX)	15%	-1	-0.15	-3	-0.45	-3	-0.45
Effectiveness per Dollar Spent	15%	3	0.45	4	0.60	5	0.75
Non-Technical	30%		1.30		1.23		1.68
Social Considerations	7.5%	4	0.30	2	0.15	5	0.38
Environmental Impact	10%	4	0.40	5	0.50	6	0.60
Regulatory Approvals (Permitting)	5%	6	0.30	4	0.20	5	0.25
Health & Safety (Flood Protection, Public Safety, Recreation, etc)	7.5%	4	0.30	5	0.38	6	0.45
	100%		2.8		2.5		3.6

Preferred Alternative


- **Alternative 3: Two pump stations**
- **Removes All City Outfalls (9)**
- **Routes Outfall 5 to Alligator Lake
(Additional WQ Treatment)**
- **Significantly Improves Nearshore Water Quality**
- **Highest Effectiveness per Dollar Spent
(100% / 77% of flows treated)**
- **Eliminates Adverse Impacts to
Environmental Resources**
- **Scalable**



Gulf of Mexico Set Up

Plan Design & Solution

Pull Pipe from Water or Land – Both can be done



Catch Rig: Universal 250x400 – will be placed on jack-up barge (#1)



-Potential Pilot Hole Rig - A

Barge and Drill Rig Gulf of Mexico Set-up



Catch Rig #1

Primary Drill #2




**American Auger DD440-T
440,000 ft/lbs of drilling thrust**

Land Side Set Up

Plan Design & Solution

Pull Pipe from Water or Land – Both can be done



Pilot Hole Construction

During progress meetings, DBE has mentioned that we would like to mobilize either a Ditch Witch JT100 or the Universal 250x400 drill rig to perform the initial pilot hole construction. For visual reference on the above graphic, these are the 2 single small lines extending from the land into the water with a curved horizontal radius.



The JT 100 is a versatile drill that allows for a small footprint to be maintained. As you can see in the photo above, this rig is able to self-load rod baskets by using its onboard crane arm, without needing a separate excavator and stack of rods that double the width of our footprint. Using the available 100,000 ft/lbs of torque (or 250,000 ft/lbs with the Uni rig), this machine will be used to construct the pilot hole, which is approximately 8-9 inches in diameter. However, during this initial portion of hole construction, the ocean floor will not be breached by the tooling. This will prevent a release of bentonite drill mud into the Gulf which could create a turbid event. A breach will not occur until a casing is installed. Moreover, DBE will turn off the down-hole mud pump when there are between 1-3 drill rods remaining before exiting the surface. This will also ensure the heavier drill mud stays within the bore hole and keeps it from collapsing.

Enlarging the Bore Hole


Once each pilot hole is constructed with the shown horizontal radius, the drill rods will be disconnected land-side and will be hooked up to a maxi rig with either 440,000 or 1.1 million ft/lbs of torque to ream and enlarge the pilot hole to approximately 42-inches in diameter. Depending on the deployment status of our maxi rigs, DBE will either mobilize the American Augers DD440-T or DD1100-RS. Each machine provides more than enough torque to ream the bore holes to prescribed diameter before readying the pipe(s) for pullback. DBE does not plan to breach the ocean floor with drill tooling until a steel conductor casing is driven from the barge into the ocean floor which will be used to contain drill mud and allow the tooling to be connected to the barge-based drill rig. The Universal 250x400 that may have been relocated from land-side to the barge after pilot hole construction (if this is the rig used), will help the land-based rig to rotate the drill string, but its main purpose will be to pull the pipes into final positioning from the ocean.

In addition to the drill rig based on land, DBE will also be placing a mud reclaimer (American Augers MCD-1000), otherwise known as a recycler within the beachside parking area during construction. This machine mixes bentonite with water to create drilling mud that is pumped through the drill stem to lubricate our downhole tooling and to build a wall cake that keeps the hole from collapsing as we push ream the hole. Through a closed loop system, the mud is flowed back from the drill head to the entry pit where it is pumped into the recycler and crosses over numerous varying sieve size screens with shakers to remove dirt, sand and other downhole particulates from the liquid mud that will be sent back to the drill head once cleaned. This prevents DBE from having to continually make more mud, which causes more waste for disposal when complete. For reference, please see the proposed site plan in page 7 below.

Recycler Unit



American Augers MCD-1000 Mud Reclaimer



Staging & Pulling Pipe

DBE intends to pull the new stormwater discharge pipes from the jack-up barge staged approximately 1,300 feet offshore of 3rd Ave. North. To accomplish this, FPVC pipe will be moved from the anticipated staging area at the WTP near the airport to the southeast corner of the Gulf Shore Blvd & 3rd Ave. North intersection. Pipe will be transported to the jobsite using a pipe trailer and offloaded in the grass a few sticks at a time. This will allow the fusion and stacking to begin. The operation is anticipated to begin just after we've initiated the pilot hole construction so that impact to the area is minimized.

Once unloaded at the construction site, DBE and Underground Solutions will close a small portion of the road to begin fusion operations, within a 200 LF portion of the southern travel lane (from west to east) along 3rd Avenue North. Pipe joints will be thermally butt fused and staged in 180 LF segments in the area identified below, within City ROW between the edge of pavement and the royal trees.

We will stack pipe in 180 LF segments a total of 3 levels high; 3 on bottom, 2 in the middle and 1 on top. Each pipe will be lashed to the others so they will not fall or slide out. These segments will be stacked on 4x4 or 6x6 lumber perpendicular to the travel lane and flow of the swale. There is a stormwater catch basin at the intersection that lies just above the existing grade of the swale. This is a likely culprit for street flooding, but by placing the lumber perpendicular, the water may continue to flow toward the catch basin, under our fused pipe segments if there is a rain event. Moreover, if the street begins to flood, DBE will have a vacuum unit onsite that can assist in sucking up overflow and discharging it directly into the storm system.

The day before each pipe pullback, DBE will close down 3rd Ave. North so that the 180 foot lengths may be fused into a single 800-900 LF segment. This segment will take up an entire travel lane of 3rd Ave. North from Gulf Shore Blvd to 3rd Street North. This leaves a single 180 LF segment left to be attached to complete the pipe string. However, DBE must close down Gulf Shore Blvd entirely to north/southbound traffic to pull the pipe across the street and into the bore entry pit. Once the segment is lying across Gulf Shore, the final piece can be fused on to complete the approximately 1,100 LF discharge line. The closings will have to occur twice to accommodate each new discharge line, a maximum of 2 days per occurrence.


The Universal 250x400 drill will extend its drill string from the exit pit on the ocean floor all the way to the entry pit on land and connect to the pipe string pull-head using a swivel. Once attached and pulled into position at the entry pit on land, DBE will begin filling the pipe with ballast water as it enters the mudline. This will reduce vertical forces on the pipe and ensure it stays at the bottom of the hole, instead of floating along the top causing more friction.


Once pulled into place, the segment will be capped for pressure testing. The drill rig(s) will be moved north or south, depending on which line is installed first for horizontal separation, and the process repeated to install the 2nd and final stormwater discharge line. Upon both lines

being pulled into final position, an official pressure test will be conducted, the ends capped under water and landside, and buried on land until the subsequent pump station construction is ready to connect onto them for commissioning.

DBE will then restore the asphalt through mill & resurfacing, replace landscaping that was disturbed, and reopen the beach parking areas on 3rd Avenue North.









TEMPORARY PEDESTRIAN WALKWAY



EXISTING CROSSWALK

SIGNALS AT GULF SHORE BLVD N

WORK AREA

WORK AREA

WORK AREA

LEO TO ASSIST WITH PEDESTRIANS CROSSING THE ROAD

LEGEND

- = WORK AREA
- = CHANNELIZING DEVICE
- = PED WALKWAY ROUTE

MOT provided by:
Bob's BARRICADES, INC.
COMPLETE WORKSITE TRAFFIC CONTROL

PLAN NOT TO SCALE

FDOT This Certifies that **CAMERON BERGER**
Has Completed a Florida Department of Transportation Approved Temporary Traffic Control (TTC) Advanced (Refresher) Course.
Date Expires: 08/20/2025 Certificate # 75723
Instructor: Ronald C. Appel FDOT Provider # 134

A&S W Consultants, Inc.
Phone: 386-798-9899
5545 Benchmark Lane
Sanford, FL 32773
www.FloridaMOT.com
nicollee@awsonconsultants.com

TEMPORARY TRAFFIC CONTROL SHALL COMPLY WITH THE CURRENT EDITION OF THE FDOT DESIGN STANDARDS (102-600 SERIES INDEX NUMBERS) AND MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (MUTCD).



PIPE FUSION & STAGING



VARIABLE MESSAGE BOARDS LABELED (A) TO DISPLAY THE FOLLOWING MESSAGE 7 DAYS PRIOR TO WORK COMMENCEMENT:

PANEL 1	PANEL 2
ROAD TO BE CLOSED	MM/DD/YY THRU MM/DD/YY

VARIABLE MESSAGE BOARD LABELED (B) TO DISPLAY THE FOLLOWING MESSAGE 7 DAYS PRIOR TO WORK COMMENCEMENT:

PANEL 1	PANEL 2
BEACH ACCESS CLOSED	MM/DD/YY THRU MM/DD/YY

TEMPORARY TRAFFIC CONTROL SHALL COMPLY WITH THE CURRENT EDITION OF THE FDOT DESIGN STANDARDS (102-600 SERIES INDEX NUMBERS) AND MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (MUTCD).

PIPE STAGING ALONG EDGE OF PAVEMENT, WITHIN UTILITY EASEMENT 180'

TEMPORARY SIGN SUPPORT NOTES:

- All signs shall be post mounted when work operations exceed one day except for:
 - Road closure signs mounted in accordance with the vendor drawing for the Type III Barricade shown on the APL.
 - Pedestrian advanced warning or pedestrian regulatory signs mounted on sign supports in accordance with the vendor drawing shown on the APL.
 - Median barrier mounted signs per Index 700-013.

LEGEND

= WORK AREA

= VARIABLE MESSAGE BOARD

MOT provided by:
BARRICADES, INC.
 COMPLETE WORKSITE TRAFFIC CONTROL

PLAN NOT TO SCALE

This Certifies that **CAMERON BERGER**
 Has Completed a Florida Department of Transportation Approved Temporary Traffic Control (TTC) Advanced (Refresher) Course.
 Date Expires: 09/20/2025 Certificate # 76723
 Instructor: Ronald C. Appel FDOT Provider # 134

A&S Consultants, Inc.
 Phone: 386-788-9899
 5545 Benchmark Lane
 Sanford, FL 32773
 www.FloridaMOT.com
 nicole@aswconsultants.com

Image © 2022 TerraMetrics



PIPE PULLBACK APPROX 8 HOUR DURATION

VARIABLE MESSAGE BOARDS LABELED (A) TO DISPLAY THE FOLLOWING MESSAGE 7 DAYS PRIOR TO WORK COMMENCEMENT:

PANEL 1	PANEL 2
ROAD-SIDEWALK TO BE	CLOSED MM/DD/YY XXAM-XXPM

TEMPORARY TRAFFIC CONTROL SHALL COMPLY WITH THE CURRENT EDITION OF THE FDOT DESIGN STANDARDS (102-600 SERIES INDEX NUMBERS) AND MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (MUTCD).



PANEL 1	PANEL 2
ROAD CLOSED AHEAD	FOLLOW DETOUR

PANEL 1	PANEL 2
S/B GULFSHOR CLOSED	FOLLOW DETOUR

PANEL 1	PANEL 2
3RD AVE W/B CLOSED	FOLLOW DETOUR

PANEL 1	PANEL 2
ROAD CLOSED AHEAD	FOLLOW DETOUR

PANEL 1	PANEL 2
3RD AVE W/B CLOSED	FOLLOW DETOUR

PANEL 1	PANEL 2
N/B GULFSHOR CLOSED	FOLLOW DETOUR

TEMPORARY SIGN SUPPORT NOTES:

- All signs shall be post mounted when work operations exceed one day except for:
 - Road closure signs mounted in accordance with the vendor drawing for the Type III Barricade shown on the APL.
 - Pedestrian advanced warning or pedestrian regulatory signs mounted on sign supports in accordance with the vendor drawing shown on the APL.
 - Median barrier mounted signs per Index 700-013.

MOT provided by:
B&B BARRICADES, INC.
 COMPLETE WORKSITE TRAFFIC CONTROL

PLAN NOT TO SCALE

LEGEND

= WORK AREA

= VARIABLE MESSAGE BOARD

FDOT This Certifies that CAMERON BERGER
 Has Completed a Florida Department of Transportation Approved Temporary Traffic Control (TTC) Advanced (Refresher) Course.
 Date Expires: 09/20/2025 Instructor: Ronald C. Appel Certificate # 76723
 FDOT Provider # 134

A&S W Consultants, Inc.
 Phone: 386-788-9899
 5545 Benchmark Lane
 Sanford, FL 32773
 www.FloridaMOT.com
 nicole@aswconsultants.com

Image © 2022 TerraMetrics

**End of
Presentation
Q & A
Thank you**