



DURING CONSTRUCTION, CONTRACTOR SHALL REMOVE BEACH SIGN, PAVERS, BIKE RACK, FENCE AND OTHER ELEMENTS IN THIS AREA AND STORE AND SAFEGUARD UNTIL READY TO REINSTALL AFTER CONSTRUCTION. CONTRACTOR SHALL THEN RECONSTRUCT THIS AREA AS DIRECTED BY ENGINEER USING THESE ELEMENTS AND UP TO 400 SF OF 6" THICK CONCRETE SIDEWALK INCLUDING HANDICAP RAMP

LEGEND:

- x SURVEY POINTS
- x LIDAR POINTS
- DESC ELEV PROPOSED GRADE
- ~ FLOW ARROW

Revision	By	Appd.	Date	Comments
1	KME	APPROVED	18.07.12	CITY OF NAPLES COMMENTS

Issued	By	Appd.	Date	Comments
ISSUED 75% DESIGN DRAWINGS TO CITY (PRELIM REVIEW)	SAH	RC	21.05.17	
ISSUED FINAL DESIGN	SAH	RC	20.02.14	
ISSUED 60% DESIGN DRAWINGS	KME	APPROVED	18.03.14	

Consultants

5801 Pelican Bay Boulevard, Suite 300
Naples, FL 34108
www.stantec.com

7201 Delaney Court
Sarasota, FL 32420
www.ericksonconsultingengineers.com

Copyright Reserved

The Contractor shall verify and be responsible for all dimensions. DO NOT scale the drawing - any errors or omissions shall be reported to Erickson Consulting Engineers (ECE) without delay. The Copyrights to all designs and drawings are the property of ECE. Reproduction or use for any purpose other than that authorized by ECE is forbidden.

Client/Project

CITY OF NAPLES
735 8th St S
NAPLES, FL

Naples Beach Restoration & Water Quality Improvement Project

File Name: 10606.C-103.dwg

MPL	SAH	RC	2022.04
Dwn.	Chkd.	Desgn.	YYYY.MM

Title

**PUMP STATION
PROPOSED PAVEMENT AND
DRAINAGE PLAN**

Project No. 177310606 Scale AS NOTED

Revision Drawing No. C-103

X:\0226\erickson\shared_projects\177310606\Drawings\01_Schematic\active\civil\sheet\10606_C-103.dwg
 2022/07/20 2:22 PM BY: LALIBON, WME